

QUOTE

St Peter's Anglican Church

Date
17 Jul 2019

Boden Building Ltd
56 Norfolk Street
Arrowtown 9302
Attn: Bod

Expiry
16 Aug 2019

Quote Number
QU-0013

Reference
Refreshing

0212793434

GST Number
98-209-336

Description	Quantity	Unit Price	Amount NZD
Joicci Decor to scrape back existing paint work, lead test, supply and repaint both buildings in same or near same colour. Excludes roof	1.00	47,500.00	47,500.00
United Scaffold to scaffold church hall building for all roof and repainting work, including 6 weeks rental	1.00	6,762.00	6,762.00
United Scaffold likewise for Vicarage	1.00	5,664.00	5,664.00
All below refers to Church hall until otherwise noted. NORTH refers to elevation facing Church St. Price is for materials and Labour	1.00	1.00	1.00
Roof, North side, to patch and repair any roofing, repair or replace spouting including to roof quirk, provide 13m of eave mould	1.00	4,930.00	4,930.00
Roof South side, Patch and repair, replace all barge flashings, smarten fascia, fix up S.W. corner timber work	1.00	3,330.00	3,330.00
South wall, Replace base mould	1.00	350.00	350.00
East Wall, replace apron flashings over porch, replace associated weatherboards, replace base mould and 1 to 2 weatherboards up from the base, overhaul both timber doors including new sill to to south side porch door.	1.00	8,660.00	8,660.00
North Wall. replace base mould and 1 weatherboard run along full length of wall plus base flashing	1.00	2,708.00	2,708.00
West wall, replace 4 number weatherboards at 4.8m	1.00	960.00	960.00
Contingency	1.00	2,500.00	2,500.00
The following refers to the Vicarage	1.00	1.00	1.00

Description	Quantity	Unit Price	Amount NZD
East wall replace window sill and facing boards	1.00	1,450.00	1,450.00
North wall, replace fascia above verandah, replace weather boards and Apron flashing above verandah,	1.00	1,900.00	1,900.00
Partial Restoration of Bay window including Base boards	1.00	4,000.00	4,000.00
Full restoration of bay window including working sashes	1.00	9,000.00	9,000.00
West and South elevation, replacing only a few weatherboards	1.00	800.00	800.00
To remove roofing iron, fit breather paper below and refasten iron with new screws,	1.00	16,500.00	16,500.00
Contingency	1.00	3,500.00	3,500.00
P'n'G including, travel, tooling, logistics, safety, phones, compliance, insurance and office time	1.00	10,000.00	10,000.00
		Subtotal	130,516.00
		TOTAL GST 15%	19,577.40
		TOTAL NZD	150,093.40